

TE Resource Management



TE resource management is defined as the tuning of certain properties on the TE interfaces to optimize the tunnel placement.

This chapter contains the following sections:

- Overview, page 4-1
- Modifying Network Resources, page 4-2
- Change Link Status, page 4-6

Overview

When a tunnel placement is attempted and there is insufficient bandwidth, sometimes the resources on the TE links can be changed and the tunnel placement retried.

Network resources in this context are understood to be routers in the TE network, the interfaces that connect them, and the RSVP bandwidths and other properties configured on the links. Since ISC TEM relies on the discovery process to add the network elements to the repository, the resources must be discovered before resource management can be performed.

TE resource management is a manual process that should be performed on an as needed basis. If the original configuration is already optimal, there is no need for the user to do any resource management tasks. If subsequent discovery unveils any discrepancy, or if you experience difficulty achieving desired results in protection planning or placing primary tunnels, adjustments on the resources may be warranted.

L

4-1

An overview of the resource management process is provided in Figure 4-1.



Figure 4-1 Resource Management Processes

Modifying Network Resources

The resource management tasks are first of all carried out from the TE Links List window.

Note

Certain attributes, such as Description, that do not impact the computation carried out by these tools and updates to these are, therefore, not displayed in the Computation Result Window.

To modify a TE link, use the following steps:

Step 1 Navigate Service Inventory > Inventory and Connection Manager > Traffic Engineering Management > Assign TE Resources. The TE Links List window shown in Figure 4-2 appears.

TE	TE Links List											
Т	TE Provider Provider2											
	Show TE Links with Device Name 💌 matching *											
#	Image: Showing 1 - 5 of 35 records Image: Showing 1 - 5 of 35 records<											
1.		isctmp11	CISCO_ROUTER	POS0/2/0/0	isctmp12	CISCO_ROUTER	POS0/3/0/0	10.2.4.10<->10.2.4.9	UP			
2.		isctmp11	CISCO_ROUTER	POS0/3/0/1	isctmp12	CISCO_ROUTER	POS0/1/0/1	10.2.4.14<->10.2.4.13	UP			
З.		isctmp11	CISCO_ROUTER	POS0/0/0/0	isctmp8	CISCO_ROUTER	POS5/0	10.2.4.6<->10.2.4.5	UP			
4.		isctmp10	CISCO_ROUTER	POS0/2/0/0	isctmp12	CISCO_ROUTER	POS0/4/0/0	10.2.4.22<->10.2.4.21	UP			
5.		isctmp12	CISCO_ROUTER	GigabitEthernet0/2/0/0	isctmp7	CISCO_ROUTER	GigabitEthernet5/0	10.2.4.29<->10.2.4.30	UP			
	Rows per page: 5 ▼ 0f 7 G 0 0 0 7 G 0 0 0 0 0 0 0 0 0 0 0 0 0											
	Close Display Details Show Tunnels v Edit v Change Status v											
	Proceed with Changes >> V Cancel											

For an explanation of the various window elements, see TE Links, page A-21.

The links list shows the current active links in the TE network. Use the arrows to page forward as needed.

- **Step 2** Select the desired link in the links list.
- **Step 3** Click **Edit > Interface A** or **Edit > Interface B** to edit one of interfaces on the link.



If a non-Cisco interface is selected for editing, changes made in the Edit window will be saved in the ISC repository but they will not be deployed.

Step 4 The TE Resource Modification window appears as shown in Figure 4-3.

I

Figure 4-3 TE Resource Modification

TE Resource Modification

SR Job ID: New		Provider: Provider2	SR ID: New
SR State: REQUESTED		Creator:	Type: ADD
Device/Interface:	isctmp11 : POS0/2/0/0		
Peer Device/Interface:	isctmp12 : POS0/3/0/0		
Description:			
_ink Bandwidth (Kbps):	2488320		
Max Global (BC0) Reservable (Kbps) ^{**} :	45000		
Max Sub Pool (BC1) Bandwidth (Kbps) [*] :	30000		
Attribute Bits (0x0-0xFFFFFFFF) *:	0x0		
TE Metric *:	2000		
Propagation Delay *:	0		
Max Delay Increase *:	0		
Link Speed Factor *:	1.0		
			Continue >> Cancel
lote: * - Required Field			

For an explanation of the various fields, see TE Links, page A-21.

Step 5 Make the desired modifications and click Continue >> to proceed to the confirmation page as shown in Figure 4-4 to verify the changes or click Cancel to quit without saving.

Figure 4-4	TE Resource Modification (Confirmation P	Page)
Figure 4-4	I E Resource Woodfication (Confirmation P	'ag

TE Resource Modification

SR Job ID: New		Provider: Provider2	SR ID: New
SR State: REQUESTED		Creator:	Type: ADD
Device/Interface:	isctmp11 : POS0/2/0/0		
Peer Device/Interface:	isctmp12: POS0/3/0/0		
Description			
Link Bandwidth (Kbps):	2488320		
Max Global (BC0) Reservable (Kbps) ^{**} :	45000		
Max Sub Pool (BC1) Bandwidth (Kbps) ^{**} :	30000		
Attribute Bits (0x0-0xFFFFFFF)	0x0		
TE Metric *:	2000		
Propagation Delay *:	0		
Max Delay Increase *:	0		
Link Speed Factor *:	1.0		
		<< Edit Proceed with Changes >>	V Save & Deploy V

Step 6 Click **<< Edit** to return to the editable window or proceed in one of the following ways:

• **Proceed with Changes >>** (Figure 4-5)—Perform Tunnel Audit or Tunnel Repair.

For a detailed explanation of Tunnel Audit and Tunnel Repair, see Chapter 6, "Advanced Primary Tunnel Management."

If a non-Cisco device is edited, **Proceed with Changes >>** will be disabled. Instead, **Save & Deploy** is enabled and the changes can be saved (not deployed).

• Save & Deploy (Figure 4-6)—If the changes made do not affect tunnel placement, click Save & Deploy to proceed. In this case, there is no need for performing Tunnel Audit or Tunnel Repair.



When you click Save & Deploy, a background process is started. To avoid a potential conflict with another deployment, wait until the SR has completed the Requested and Pending states before deploying another SR with Save & Deploy. To see the state of deployment, go to the Service Requests window under **Inventory and Connection Manager** > Service Requests or open Monitoring > Task Manager.

Figure 4-5 TE Links List - Proceed with Changes

Proceed with Changes >> 💡					
Tunnel Audit	L	B			
Tunnel Repair	1000	0771			

I



For an explanation of the options available under **Proceed with Changes** >> and **Save & Deploy**, see Edit Interface, page A-27



Force Deploy

In ISC TEM, service requests (SRs) are generally deployed from each TE service, not from the Service Requests page in Inventory and Connection Manager with the exception of the TE Traffic Admission SR.

After deployment, the SR status can be viewed from the SR window at Service Inventory > Inventory and Connection Manager > Service Requests.

For more information on working with service requests, see Appendix B, "Managing Service Requests."

If the SR does not go to the **Deployed** state, go to the Task Log to see the deployment log (Monitoring > Task Manager > Logs). Task logs are further described in TE Task Logs, page 10-1.

Change Link Status

From the TE Links List window (Figure 4-2), you can also find out what effect it will have if a link is taken offline. This approach can be used to move tunnels off a link before actually shutting down the interface.

۵,

Note Link status in ISC TEM is of local significance. Changing link status as described in this section is not provisioned down to the network.

To change the link status, use the following steps:

Navigate Service Inventory > Inventory and Connection Manager > Traffic Engineering Step 1 Management > Assign TE Resources.

The TE Links List window appears.

Step 2 Select one or more links and click the Change Status button as shown in Figure 4-7.

ΓE	E Links List									
TE Provider Provider2										
Show TE Links with Device Name 💌 matching *										
¥		End Device A	Туре	Interface A	End Device B	Туре	Interface B	Showing Label	g 1 - 5 of 35 red Adm Statu	cords in IS
	•	isctmp11	CISCO_ROUTER	POS0/2/0/0	isctmp12	CISCO_ROUTER	POS0/3/0/0	10.2.4.10<- ≻10.2.4.9	UP	
2.		isctmp11	CISCO_ROUTER	POS0/3/0/1	isctmp12	CISCO_ROUTER	POS0/1/0/1	10.2.4.14≺- ≻10.2.4.13	UP	
3.		isctmp11	CISCO_ROUTER	POS0/0/0/0	isctmp8	CISCO_ROUTER	POS5/0	10.2.4.6<->10.3	2.4.5 UP	
ŀ.		isctmp10	CISCO_ROUTER	POS0/2/0/0	isctmp12	CISCO_ROUTER	POS0/4/0/0	10.2.4.22≺- ≻10.2.4.21	UP	
5.		isctmp12	CISCO_ROUTER	GigabitEthernet0/2/0/0	isctmp7	CISCO_ROUTER	GigabitEthernet5/0	10.2.4.29<- ≻10.2.4.30	UP	
	Ro	ws per page	5 💌				I ₫ ₫ Go	to page: 1	of 7 😡 🕻	>D0
Close Display Details Show Tunnels V Edit V Change Status V										
	Proceed with Change Disable Di									

For an explanation of the various window elements, see TE Links, page A-21.

- **Step 3** Select **Enable** or **Disable** to enable or disable the selected link.
- **Step 4** As an example, selecting **Disable** will change the link status to **DOWN** as shown in Figure 4-8.

Figure 4-8 Link Status Down

1. 🔽 isctmp11 CISCO_ROUTER POS0/2/0/0 isctmp	2 CISCO_ROUTER POS0/3/0/0	10.2.4.10<- >10.2.4.9	DOWN
--	---------------------------	--------------------------	------

Similarly, use Enable to change the status back to UP.

Step 5 Click Proceed with Changes >> to assess any impact on tunnel placement using Tunnel Audit or Tunnel Repair and deploy the changes (see Figure 4-9).



Proceed with Ch	anges >> 🔤	•
Tunnel Audit		_ ي
Tunnel Repair		1226

For a detailed explanation of Tunnel Audit and Tunnel Repair, see Chapter 6, "Advanced Primary Tunnel Management.".

I